





Always check the website for the most updated specifications: [www.americh.com](http://www.americh.com)All bathtub dimensions are  $\pm 1/2"$ .

## Airbath System II

**LEGEND:****B** BLOWER

● ON/OFF CONTROL

— ACCESS PANEL (PROVIDED BY FACTORY)

**STANDARD EQUIPMENT:**

- Integral Waste & Overflow with Polished Chrome trim  
Available with polished brass, polished nickel, satin nickel or oil rubbed bronze trim at no additional charge if specified at the time of order. Requests after order is shipped are subject to a \$75 list charge for trim
- Lift bag is provided

**INSTALLATION TIPS**

- Install according to Owner's Manual and local codes.
- Access panel for Airbath® systems included with the Contura series.
- Hot water supply should be 65-75% of tub capacity or greater.
- Always consult your local plumber for recommendations as installations will vary.

**DIMENSIONS:**

66" x 32" x 24" (1676 x 813 x 610 mm)

Gallon to Overflow = 68 (Liters = 257)

Factory installed integral drain.

**MATERIAL:** Acrylic (White and Biscuit Only)**TUB FLOOR:** Non-Textured**UNDERMOUNT:** No**ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

**OPTIONAL ACCESSORIES**

- Chromatherapy
- Linear Overflow
- Remote Control Upgrade

**CODES AND COMPLIANCE**

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories - Canada (cUL)
- Canadian Standards Association - (CSA)
- ANSI Z124.1 • ANSI A112-19.7 • ANSI A112.19.8

Contact Americh for additional approvals.